



DEMOLITION
ABANDONED HARNETT COUNTY SEWER PLANT
Addendum No. 2

To: Prospective Contractors
From: Ben Nuesmeyer, Capital Project Manager
Date: May 22, 2017
Project: Demolition Abandoned Harnett County Sewer plant

All Prospective Contractors are hereby notified of the following additions and clarifications for the referenced project:

Item # 1:

Contractor shall prepare their bid to include bricking up and sealing off with concrete any pipes that are concrete in lieu of installing a permanent cap. All other pipes to be terminated will be done with an MJ cap.

Item # 2:

Contractor will be required to core drill holes in the slabs of the Basins and Clarifiers. The amount of holes and size needed will be at the recommendation and the past experience of the contractor.

Item # 3:

Payment to the contractor will be made in two equal installments. When contractor is 50% complete as deemed by Harnett County Capital Project Manager and when contractor is 100% complete.

Item # 4:

Contractor will be required to make flush with the existing concrete slabs in the Basin and Clarifiers any pipes protruding thru the floors. There should be one in each one of the structures.

Item # 5:

The time limit for this project is 120 calendar days.