

**COUNTY OF HARNETT**

**PROJECT ADDENDA #1  
ROOF REPLACEMENT**

**Generator Room,  
Metro High Service,  
Wake High Service  
310 W. Duncan St.  
Lillington, North Carolina  
27546**

**December 7, 2017**

A pre-bid conference was held on December 6, 2017 for the Roof Replacement at Harnett Water Treatment; buildings Generator Room, Metro High Service and Wake High Service. The purpose of this addendum is to respond to contractor requests for clarification during the pre-bid conference. Approved changes to or clarification of the project manual as follows:

1. The following items are meant to clarify or change various aspects of the General Requirements, Scope of Work, and Specifications.
  - a. Metro High Service Building is a concrete deck as indicated on page 12 of the project manual
  - b. Metro High Service Building replace 4x14 overhang, replace with tapered insulation sloping all towards existing scupper. Install base layer of SBS modified base sheet in hot type III asphalt and cap layer of SBS modified base sheet in hot type III asphalt and alumizer like all other roof sections.
  - c. Metro High Service Building: Remove existing exhaust fan as noted on walk through, lay 20 gauge steel and fasten to existing concrete deck
  - d. Generator Room Building has existing metal deck as indicated on page 12 of the project manual
  - e. Wake High Service Building has a concrete deck as indicated on page 12 of the project manual.
  - f. Wake High Service Building: Remove existing conductor boxes and down spouts and install full gutter system and new down spouts; One (1) on each side of the building with a total of Four (4)
  - g. Metal Edge on all Three (3) above building, metal edge is replaced not existing wall panel directly below metal edge.