Finance Department

PO Box 760
455 McKinney Parkway
Lillington, NC 27546

Phone: 910-893-7557
Fax: 910-893-3445

www.harnett.org

IT OFFICE UPFIT RFP

HARNETT COUNTY

Addendum #2

TO: Prospective Vendors

FROM: Renea Warren-Ford, Finance

DATE: November 3, 2026

PROJECT: IT Office Upfit RFP

NOTICE: All Prospective Vendors, please see questions and answers pertaining to the IT office upfit RFP below.

1. Drawing G-005 specifications Section 09.300 Resilient Tile Flooring subsection 09.301 references polymer modified cement based self-leveler to be applied. What is the intended purpose of this and is it to help with the previously sealed concrete floors? Does someone know what type of sealer was used and how long it has been installed?

   The purpose of the self-leveler surface preparation is to address irregularities and minor slopes in the existing concrete flooring surface, as this was originally designed as a manufacturing/warehouse space. We are not in possession of any sealer types that were utilized during the original construction or subsequent use of the facility. The successful contractor will provide surface testing of the existing concrete and provide a report with flooring preparation recommendations for review by the County prior to flooring installation.

END DOCUMENT